

# 상용 원자로 물리 시험 기준 및 결과 분석 Reactor Physics Test Criteria & Results Analysis

2016. 10. 26  
Sang-Weon Park

KEPCO NF, 워크샵 : 노물리 시험과 분석

## CONTENTS



- ☐ DOCUMENTS REVIEWED
- ☐ INTRODUCTION
- ☐ TEST OBJECTIVES & BASES
- ☐ PROBLEM CATEGORIES
- ☐ STAR PROGRAM
- ☐ DOMESTIC UNEXPECTED TEST RESULTS
- ☐ TEST CRITERIA
- ☐ INITIAL CORE RESULTS ANALYSIS
- ☐ CODE PERFORMANCE
- ☐ SUMMARY & DISCUSSION

- ❑ ANSI/ANS-19.6.1-2011 : reload startup physics test for pressurized water reactors
- ❑ STAR (Startup Test Activity Reduction) Program WCAP-16011-NP-A
- ❑ ICD Startup Report Evaluation Report for HB3&4, SK1&2, SW1&2
- ❑ Core Performance and Anomalous Data Resolution Training Materials (1997)
- ❑ Many Startup Test Report Summary (Downloaded by Google Search)

## INTRODUCTION (1/2)

- ❑ Test Objectives
  - To determine if the measured reactor physics parameter is consistent with the design predicted value
  - May be used to establish appropriate operating limits or to determine compliance with appropriate Technical Specifications
  - Deviations would indicate a problem with either the as-built reload core or the design calculations
- ❑ Test Classification
  - FOAK (First of a Kind) vs Follow on Unit : Initial Core
    - ✓ Hanbit Unit 3, SK3
    - ✓ Hanbit Unit 4,5,6, Hanul 3,4,5,6, SK1,2, SW1,2, SK4,5,6
  - Initial Core vs Reload Core
  - Zero Power vs Power Ascension

### ❑ Test Criteria Bases

- Based on differences between calculations and measurements that would suggest a problem with the as-built core, the measurement, or the prediction (Something may be wrong)
- Not established by rigorous analysis of the test methods or design models
- The ideal criterion to be used is tight enough such that no design anomaly would go unnoticed but loose enough such that typical differences would not violate the criterion
- Be established assuming that known biases are accounted for in the predictions before comparisons are made

### ❑ HZP CBC

- To confirm the reactivity balance
  - ✓ [Tech. Spec. SR 3.1.3.1](#)
- Measures the overall reactivity of the reactor and validates the accuracy of the predicted criticality calculations
- This verification ensures that predicted shutdown boron concentrations provide the necessary margin to criticality to meet operability requirements
  - ✓ [Minimum Boron Concentration for SDM Requirement](#)
- This test provides verification that soluble boron sources provide adequate negative reactivity as modeled in the accident analysis

### ❑ Control rod worth

- To confirm the capability to shut down and control reactivity
- It demonstrates that the reactivity worth of the safety and regulating control rods is consistent with predictions
- This test provides a level of assurance that the fuel and core components are configured consistent with design assumptions
  - ✓ Predicted Power Distribution (peaking factors)
  - ✓ Core Loading (Assemblies and Inserts)
  - ✓ Control Rods Properly attached to drive line
- The total safety and regulating control rod worth verifies adequate shutdown margin capability
- Control rod group worths and shapes provide initial indication of an acceptable power distribution
- This test represents the only opportunity to verify that the rod worths are consistent with those assumed in the shutdown margin calculations and in the safety analysis for the core

### ❑ ITC

- To confirm the reactivity control characteristic
- The test demonstrates that the reactivity response to temperature changes in the reactor core is consistent with design predictions
- To compare to Tech. Spec. Values at HZP
- Measured MTC = Measured ITC - Predicted FTC

### ❑ Flux Symmetry

- To confirm that the power distribution in the core is consistent with design predictions at low power
- This measurement may reveal core anomalies (e.g., dropped rods, detached rod fingers, fuel misloadings, flow anomalies, etc.)



### ☐ Power Distribution

- To confirm that the power distribution is consistent with design predictions at low, intermediate, and high power levels
- The measurements verify that the power distribution is within its design and licensing bases, and they may identify any power distribution anomalies
- These measurements provide comprehensive assurance that the fuel and core components are configured consistent with design assumptions
- Level of confidence : Bank Worth (minimal), Flux Symmetry (Good), Direct Power Distribution (Best)
- A direct power distribution measurement is necessary before exceeding 50% of full power to provide a high level of confidence that unforeseen power distribution anomalies will not result in violations of design assumptions

### ☐ Power Distribution

- Demonstrate that maximum power peaking factors are below TS limits
  - ✓ All WH plants have  $F_{\Delta H}$  surveillance requirements
  - ✓ Some plants have FQ SR including OPR1000 & APR1400, others have Fxy SR to determine FQ acceptance
- Confirm the conservatism of measured Fxy is are below value installed in COLSS/CPC (OPR&APR)

### ☐ To verify that the core behavior is as designed and to verify adequacy of physics models used to generate safety analysis input

- Radial power distribution
- Axial Power Distribution (OPR&APR)
- Core Fxy, Fr, Fz, and Fq (OPR&APR)

### ☐ HZP to HFP reactivity

- To ensure the power defect is consistent with design predictions and operability requirements for shutdown margin
- This test incorporates a number of reactivity effects : xenon, moderator temperature, fuel temperature, soluble boron worth

## STAR PROGRAM (1/2)

### ☐ Startup Test Activity Reduction (STAR) : licensed in Feb. 2005

#### ☐ STAR Program Tests

- Eliminated from Generic Program
  - ✓ CEA Worth
  - ✓ ITC at HZP
  - ✓ MTC at HZP
- Added to Generic Program
  - ✓ Alternate MTC Surveillance at HZP
  - ✓ ITC at Intermediate to HFP
  - ✓ Applicability requirements (core design, fabrication, refueling, startup testing, CEA lifetime)
- Submit a summary report included
  - ✓ Identify the core design method used
  - ✓ Compare the measured and calculated values and the differences between these values to the corresponding core design method uncertainties and
  - ✓ Show compliance with the STAR applicability requirements

### ☐ Review Criteria

- Based on differences between calculations and measurements
- Not based on the Safety Analysis
- Two-sided tolerances
- Be used to identify measurement or design errors
- Failure of any one test criterion does not necessarily warrant stopping the testing process or power ascension
- ANS WG believes that it is prudent to address these test criteria as part of a continuing evaluation of the design and measurement processes

### ☐ Acceptance Criteria

- Those criteria that have a direct link to the Safety Analysis or are defined by Technical Specifications
- One-sided tolerances
- Be constructed from Safety Analysis or related assumptions
- Failure of these criteria should not prevent further testing at the current power plateau for supporting information
- Resolution of a failure is often performed under established procedures (e.g., Technical Specification action statements)
- The established procedures will typically stipulate the power ascension requirements


## TEST CRITERIA (3/5)

### ❑ Reload Physics Test (WEC Recommendation)

Item	Review Criteria	Acceptance Criteria	Basis
ARO CBC	$\pm 500$ pcm	$\pm 1000$ pcm	SR 3.1.3.1
ITC	$\pm 3.6$ pcm/ $^{\circ}\text{C}$	MTC Tech. Spec. Limit	SR 3.1.4.1
Rod Swap Method	Ref. : $\pm 10$ % Test : 15% or 100 pcm Total RW : $\pm 10$ %	Ref. : $\pm 15$ % Test : 30% or 200 pcm Total RW : -10 %	WCAP, Available SDM
Sequential Dilution Method	15% or 100 pcm Total RW : $\pm 10$ %	Total RW : -10 %	
DRWM	15% or 100 pcm Total RW : $\pm 8$ %	Total RW : -8 %	
Power Distribution	$\pm 0.1$ RPD 5% RMS (Radial, Axial)	-	
Peaking Factor (Fxy, Fr, Fz, FQ)	10,10,10,10%	< COLSS/CPC Fxy, < Tech. Spec. FQ	CE Plants

## TEST CRITERIA (4/5)

### ❑ Action Procedure (Rod Worth)





## TEST CRITERIA (5/5)



### ❑ Reload Physics Test (Recommendation)

Item	Review Criteria (OPR,APR)	Review Criteria (WH)	Acceptance Criteria (OPR/APR, WH)
HZP/HFP CBC & HFP-HZP CBC	$\pm 500$ pcm	Same	$\pm 1000$ pcm
ITC	$\pm 3.6$ pcm/°C (or Code Unc. pcm/°C)	$\pm 3.6$ pcm/°C	MTC Tech. Spec. Limit
Rod Swap Method	Ref. : $\pm 10$ % Test : 15% or 100 pcm Total RW : +10,-6.52 %	Ref. : $\pm 10$ % Test : 15% or 100 pcm Total RW : $\pm 10$ %	Ref. : $\pm 15$ % Test : 30% or 200 pcm Total RW : -6.52, 10 %
Sequential Dilution Method	15% or 100 pcm Total RW : +10,-6.52 %	15% or 100 pcm Total RW : $\pm 10$ %	Total RW : -6.52 % Total RW : -10 % (WH)
DCRM	15% or 100 pcm Total RW : +8,-6.52 %	15% or 100 pcm Total RW : $\pm 8$ %	Total RW : -6.52 % Total RW : -8 % (WH)
Power Distribution	$\pm 0.1$ RPD 5% RMS (Radial, Axial)	$\pm 0.1$ RPD 5% RMS (Radial)	-
Peaking Factor (Fxy,Fr,Fz,FQ)	10,10,10,10%	-	< COLSS/CPC Fxy, < Tech. Spec. FQ < Tech. Spec. FΔH,FQ

## INITIAL CORE RESULTS ANALYSIS (1/6)



- ❑ Plants/Units : U5,6, SK1,2, SW1,2 Initial Core
- ❑ HZP Physics Test Item
  - ARO CBC
  - B-in CBC
  - ARO ITC
  - Individual Rod Worth
  - Total Rod Worth
  - Boron Worth
- ❑ Review of Measurement Data & Difference Between Prediction and Measurement Data

- ❑ Clear Explanation of the purpose and bases of physics tests
- ❑ To be defined clearly two level criteria for the evaluation of the test results
  - Test (Review) Criteria
  - Acceptance Criteria
- ❑ The consensus on procedure and criteria are required through the continuous communication between vendor, utility and regulator