

KOREA  
ATOMIC  
ENERGY  
RESEARCH  
INSTITUTE

# MARS-KS Analysis on an Integral Effect Test of CLOF (Complete Loss of RCS Flowrate) for the SMART Design

Hyun-Sik Park, Jin-Hwa Yang, Byong-Guk Jeon, Hwang Bae

5/13/2024

A nuclear research institute  
**reshaping the future** based on  
**peoples trust**

**KAERI**

Korea Atomic Energy Research Institute

CONTENTS

**01** INTRODUCTION

**02** SIMULATION RESULTS  
ON THE CLOF TEST

**2.1 Nodalization and Input Preparation**

**2.2 Steady-State Calculation Results**

**2.3 Sequence of Events for the CLOF Scenario**


**2.4 Transient Calculation Results**

**03** CONCLUSIONS



Korea Atomic Energy  
Research Institute

KOREA  
ATOMIC  
ENERGY  
RESEARCH  
INSTITUTE



01

Introduction

# Introduction

- **A set of integral effect tests** were successfully performed to provide data to assess the capability of the system analysis code **for the SMART design using the SMART-ITL facility.**
- Among them there is **a complete loss of reactor coolant system (RCS) flow rate (CLOF) scenario.**
  - The steady-state conditions were achieved to satisfy initial test conditions presented in the test requirement, its boundary conditions were accurately simulated using the SMART-ITL facility.
  - The CLOF scenario for the SMART design was also reproduced properly.
- Previously **a similar test** was performed for the CLOF scenario with the **VISTA-ITL** facility and was analyzed using the best-estimate system analysis code of **MARS-KS** to provide a reasonable simulation results against the measured thermal-hydraulic data.
- In this paper, the **test results from the SMART-ITL** were analyzed using the **MARS-KS** code to assess its capability to simulate a **CLOF scenario for the SMART design.**

# Introduction

## PIRTs for SMART

- Cross Reference Matrix of Major Phenomena with High Importance for Selected Accident Scenarios for SMART (B.D. Chung, 2009)

Thermal-Hydraulic Phenomena	Highest Importance Rank	Lowest Knowledge Level	Accident Scenarios		
			MSLB	CLOF (TLOF)	SBLOCA
Critical Flow (Break)	5	5	•		•
Neutron Flux	5	5	•	•	•
Decay Heat	5	5	•	•	•
Variation of Gap Heat Conductance	5	4	•	•	•
Boiling Heat Transfer in Nuclear Fuel	5	4			•
Flow Mixing in Flow Mixing Head Assembly (FMHA)	5	3	•	•	•
Reactivity Feedback Effect in Reactor Core	5	5	•	•	
Variation of Multi-D Power Distribution in Core	5	5		•	
Pump Coast-down	5	4		•	•
Pressure/Level Increase/Decrease in Steam PRZ	5	5	•	•	
SI Pump Startup, Injection Characteristics	5	5			•
Convective Heat Transfer in Nuclear Fuel	4	5	•	•	
Phase Separation in the Upper Part of Reactor	4	4			•
SG Shell-side Heat Transfer (or Asymmetric Effect)	4	5	•		•
SG Tube-side Heat Transfer	4	3	•		•

# Introduction

## Event Category for SMART100

### Representative Design Basis Events for Each Event Category (Y.J. Chung, 2012)


Event category	Representative event
15.1 Increase in Heat Removal by the Secondary System	Main Steam Line Break (MSLB)
15.2 Decrease in Heat Removal by the Secondary System	Feedwater Line Break (FLB)
15.3 Decrease in Reactor Coolant System Flow Rate	Complete Loss of Reactor Coolant Flow (CLOF, or TLOF)
15.4 Reactivity and Power Distribution Anomalies	Control Rod Assembly Ejection Accident (REA)
15.5 Increase in Reactor Coolant Inventory	Pressurizer Level Control System Malfunction (PLCSMF)
15.6 Decrease in Reactor Coolant Inventory	Small-Break Loss-of-Coolant Accident (SBLOCA)



# Introduction

## CLOF Scenario in SMART100

### Progress of CLOF scenario



Steady-state operation



RCPs stop due to emergency power loss.



Natural Circulation occurs in the primary loop.



Natural Circulation starts in PRHRS also.

Single-phase NC (in RCS) &  
Two-phase NC (in Secondary Loop)





# Introduction

## CLOF-01 Test: Transient Data



### Progress of CLOF scenario (J.H. Yang, 2018)

PZR  
pres.





FW  
flowrate

RCS  
flowrate



RCS  
fluid  
temp.

FW  
flowrate



Steam/  
FW  
fluid  
temp.



Korea Atomic Energy  
Research Institute

KOREA  
ATOMIC  
ENERGY  
RESEARCH  
INSTITUTE



02


# Simulation Results on the CLOF Test

# Simulation Results on the CLOF Test



## Nodalization and Input Preparation

### MARS-KS nodalization for the SMART-ITL: Overview




# Simulation Results on the CLOF Test



## Nodalization and Input Preparation


- MARS-KS nodalization for the SMART-ITL: RCS




# Simulation Results on the CLOF Test

## Nodalization and Input Preparation

### Estimation of Heat Loss Coefficient




### Calculation of Heat Loss Coefficient



$$\dot{Q} = \frac{T_{\infty 1} - T_{\infty 2}}{R_{total}} \quad (W)$$

#### Parameters

- $h_1$  : fluid HTC
- $h_2$  : ambient HTC
- $k$  : conductivity for pipe wall




# Simulation Results on the CLOF Test

## ❏ Nodalization and Input Preparation

### ■ Heat Structure - Helical Coiled SG

- Left/Right BC: Table 9.16-1, Card 501 / Table 9.17-1, Card 601
- Word 3: Convection Boundary Type (Left: Tube; Right: Shell)

Word 3	Geometry Type
1, 100, 101	Default
<b>114</b>	<b>Helical S/G tube side (set Dc/di on 801/901 card Word 10)</b>
135	Helical S/G shell side (set P/D on 801/901 card Word 10)
<b>160</b>	<b>Zukauskas heat transfer correlation for staggered bundle cross flow shell side</b>
161	Zukauskas heat transfer correlation for staggered and finned bundle cross flow shell side
162	Zukauskas heat transfer correlation for in-lined bundle cross flow shell side



Tube arrangement in a bank:  
(a) in-lined, (b) staggered

- Word 10: Rod or tube pitch-to-diameter ratio. The default is 1.1;
  - (Dc/di): Helical Circle Diameter-to-Tube Inner Diameter Ratio
- Modified in MARS-KS 2.0 version (Consulted by Dr. C. W. Choi (2021.6.))

# Simulation Results on the CLOF Test

- **Steady-State Calculation Results: ICs / BCs / Heat Balance**
  - **Brief setting of initial / boundary values (from measurement values)**
    - Pressure : Pressurizer & Steam line
    - Temperature : Core inlet-outlet & SGP inlet-outlet
    - Flow rate : RCP RPM (Measured at cold leg), Feedwater pump (FW line)
    - Level : Pressurizer
    - Heater power : Core (Average & Hot)
    - Heat Loss (HTC of Heat Structure) : Sectional estimation
      - CL, RPV(UDC+LDC), PZR, PSIS (PBL), PRHRS (ECT)
  - **Heat Balance between RCS and Secondary System**
    - Core power & FW flowrate
    - Achieve constant temperatures adjusting heat loss (using HTC of heat structure)
  - **Reactor Coolant System Parameters**
    - PZR water level: control using letdown and spray control variables (initial value: @C180)
    - PZR pressure and temperature: PZR heaters
    - Temp. diff. of Core/SGP inlet & outlet: RCS flow rate adjusting RCP RPM
  - **Secondary System Parameters**
    - Steam & FW line pressures
      - SGS inlet : K factor of junction @C619, C719, C819, and C919
      - SGS outlet : Steam line boundary (@TDBC 698)
    - Feedwater line (SGS inlet) flowrate using FW pumps
    - Feedwater line (SGS inlet) temperature @C610, C710, C810, and C910

# Simulation Results on the CLOF Test

## Steady-State Calculation Results: Optimization

### SS calculation with MARS-KS 1.4 ('17~'18)

Cases	Calculation Conditions
⊙	Previous Calculation
①	RCP spec. / Actual RPM (SMART-ITL pump (Canned Motor) spec. & Heat loss distribution in RCS)
②	RCP spec. / Modified RPM
③	RCP spec. / Modified RPM + heat loss location (Lower DC→CL)
④	③ + HTC optimization (CL: 206.5 & PZR: 5 & HL & wall: 2)
⑤	④ + SMART-ITL Homologous Curve
⑥=SS1	④ + SMART-ITL Homologous Curve + tuned loss coefficient (from F103: SBLOCA case)

### SS calculation with MARS-KS 2.0 ('23~'24)

Cases	Calculation Conditions
⑥=SS1	Previous Calculation
⑦	⑥ + RCP RPM tuning (to fit initial RCS flowrate)
⑧	⑦ + PZR backup heater limit (15.0 MPa, PZR pressure)
⑨=SS2	⑧ + Core power tuning
⑩=SS2c2f4	⑨ + HCSG=114(tube), 160(shell); PZR(15.05)+Table 123(HTC=140); RPM=1.0



# Simulation Results on the CLOF Test

## Steady-State Calculation Results

- Comparison of the major parameters under a steady state condition

Parameter	Target value	Test Data	MARS Cal.	Error (%)
Power, MW	1.49	1.67	1.67	0.02%
1 <sup>st</sup> Flowrate, kg/s	10.233	11.624	11.622	-0.02%
PZR pres., MPa	15.00	15.05	15.05	0.00%
PZR fluid Temp., °C	342.2	340.4	340.8	0.11%
SG 1 <sup>st</sup> inlet Temp., °C	320.9	320.6	320.6	-0.01%
SG 1 <sup>st</sup> outlet Temp., °C	295.5	298.1	296.0	-0.70%
F.W. flow-rate, kg/s	0.778	0.769	0.768	-0.13%
SG 2 <sup>nd</sup> inlet pres., MPa	6.71	5.71	5.67	-0.68%
SG 2 <sup>nd</sup> inlet Temp., °C	230.0	230.2	230.0	-0.09%
SG 2 <sup>nd</sup> outlet pres., MPa	5.62	5.62	5.63	0.13%
SG 2 <sup>nd</sup> outlet temp., °C	≥ 301.4	314.7	320.5	1.84%
SG 2 <sup>nd</sup> superheat, °C	≥ 30.0	43.3	49.1	+5.8°C

# Simulation Results on the CLOF Test


- **Sequence of Events for the CLOF Scenario**
  - **Comparison of a major sequence of a CLOF test**

Event	SMART	SMART-ITL -Test (s)	SMART-ITL -Simulation (s)
Transient initiation	RCP coast-down	0	0
Trip signal	RPS (or HPP)	0.37	0.38
Reactor trip signal & FW stop	RPS + 1.1 s	1.47	1.48
PRHR actuation signal (PRHRAS) & CMTAS	RPS + 1.1 s	1.47	1.48
Control rod insert	RPS + 1.6 s	1.97	1.98
CMT Isolation Valve open	RPS + 2.2 s	2.57	2.58
PRHRS IV open	PRHRAS + 5.0 s	6.47	6.48
MSIV/FIV close	PRHRAS + 5.0 s	6.47	6.48
Test end	$T_{RCS} < 215^{\circ}\text{C}$ (or less than 36 hours)	8,120	9,495


# Simulation Results on the CLOF Test

## Transient Calculation Results

- The core power is well simulated. (Boundary Condition)
- The heat balance through SG is reasonable.
  - Some fluctuation is observed between 6,000~8,000 s and thereafter the heat transfer is more active than the test data.



Core Power



Heat Balance through SG

# Simulation Results on the CLOF Test


## Transient Calculation Results

### Pressurizer pressure is well simulated in general but is under-predicted in the later phase.


- It is noted that the heat transfer characteristics between primary and secondary system is changed between 4,000~6,000 s in the test data.
- The decrease rate of RCS pressure tends to reduce until 3,000 s but thereafter it turns to be steeper. It becomes slower after 6,000 s.

### Secondary system pressure is well simulated.

- Its peak pressure is a little higher.



Pressure @ Pressurizer




Pressure @ SG Secondary

# Simulation Results on the CLOF Test


## Transient Calculation Results

### Fluid temperatures both in the primary and secondary sides of SG show the similar trends.

- The primary side temperatures decrease a little slowly in the MARS calculation. It keeps higher temperatures after 4,000 s.
- The recovered FW temperature is higher in the MARS calculation due to its high temperature in the primary side.



Temperature @ SG Primary




Temperature @ SG Secondary


# Simulation Results on the CLOF Test

## Transient Calculation Results

- **The MARS code predicts lower mass flow rate than the test data in the primary loop of RCS.**
  - It predicts the mass flow rate in RCS very well until 4,000 s but thereafter the under-prediction increases with the maximum difference of about 26% and the difference at 10,000 s is about 16%.
- **The MARS code predicts higher mass flow rate than the test data in the secondary loop of FW-SG-MS-PRHRS.**
  - It predicts the mass flow rate in PRHRS very well until 4,000 s but thereafter it over-predicts the test data. The maximum difference is about 14% at 10,000 s.




Mass flow rate @ RCS (CL)




Mass flow rate @ Main FW

# Simulation Results on the CLOF Test


- Transient Calculation Results (Ref: VISTA-ITL, 2017)
  - It is similarly observed during the CLOF test using VISTA-ITL.



MARS-KS nodalization for the VISTA-ITL




Core power




Pressurizer pressure

# Simulation Results on the CLOF Test


## Transient Calculation Results (Ref: VISTA-ITL, 2017)




**SG 1ry outlet temp.**




**2ry system pressure**




**2ry system flowrate**



**RCS flowrate**



**2ry system steam temp.**



**SG heat transfer**





Korea Atomic Energy  
Research Institute

KOREA  
ATOMIC  
ENERGY  
RESEARCH  
INSTITUTE




03

Conclusions

# Conclusions

- An integral effect test for the CLOF scenario was successfully performed to provide data to assess the capability of the system analysis codes of MARS-KS for the SMART design.
- The CLOF test results were simulated using the MARS-KS code to assess the simulation capability for the CLOF scenario of the SMART design.
- In overall the measured thermal-hydraulic data from the test were properly simulated using the MARS-KS code.
- However, there are still some discrepancy between the test and simulation results such as higher RCS temperatures, difference of flow rates in the later phase, etc.
- It is estimated that more accurate simulation is possible with further consideration on the heat loss through the heat structure, flow resistance in the primary and secondary loops, heat transfer rate through HCSG, etc.



A nuclear research institute  
**reshaping the future** based on  
**peoples trust**

---



# THANK YOU